

DELAWARE COUNTY, OHIO

WOODS OF GLEN ERIN

SANITARY SEWERS

2020



COUNTY MAP

SCALE: NONE

STANDARD DETAIL DRAWINGS

- Sa.S-1 - TYPICAL TRENCH (RIGID AND FLEXIBLE PIPE)
- Sa.S-2 - TYPICAL BACKFILL
- Sa.S-3 - PRECAST CONCRETE MANHOLE (TYPE A, TYPE B, TYPE C)
- Sa.S-5 - MANHOLE FRAME AND COVER CASTING
- Sa.S-6 - TYPICAL WATERTIGHT MANHOLE CASTING
- Sa.S-7 - MANHOLE STEPS AND CHANNEL
- Sa.S-8 - DROP PIPE AT MANHOLE
- Sa.S-11 - 6" SANITARY SEWER SERVICE (MAIN LINE TO R/W)
- Sa.S-15 - TYPICAL RISER
- Sa.S-16 - TYPICAL CLEANOUT
- Sa.S-20 - WATERLINE CROSSING
- Sa.S-26 - TYPICAL PRESSURE PIPE LOWERING
- Sa.S-31 - GRINDER PUMP INSTALLATION
- Sa.S-32 - CONCRETE SIDEWALK AND BERM REPLACEMENT
- Sa.S-33 - TEMPORARY PAVEMENT REPLACEMENT
- Sa.S-34 - PERMANENT PAVEMENT REPLACEMENT
- Sa.S-35 - DRIVEWAY PAVEMENT REPLACEMENT

REVISIONS

DATE	COMMENTS

DRAWING SET STATUS


- ☒ PRELIMINARY ENGINEERING SET
- ☐ ISSUED FOR BIDDING SET
- ☐ ISSUED FOR CONSTRUCTION SET
- ☐ AS-BUILT DOCUMENT SET

PLANS PREPARED BY :


PRIME AL
8415 PULSAR PLACE | SUITE 300
COLUMBUS, OH 43240
P 614-839-0250 | F 614 839 0251

DRAWING COORDINATES ARE GRID VALUES, BASED ON THE OHIO STATE PLANE COORDINATE SYSTEM, SOUTH ZONE (NAD83), AS ESTABLISHED BY GPS SURVEY.


SOURCE BENCHMARK:
OHIO DEPARTMENT OF TRANSPORTATION C.O.R.S. STATION "COLB" LOCATED AT THE ODOT CENTRAL OFFICE GARAGE COMPLEX.
ELEV: 611.63 (NAVD88)



PROJECT AREA



LOCATION MAP



DELAWARE COUNTY APPROVAL

THE SIGNATURES BELOW SIGNIFY ONLY CONCURRENCE WITH THE GENERAL PURPOSE AND LOCATION OF THE PROPOSED IMPROVEMENT. ALL TECHNICAL DETAILS REMAIN THE RESPONSIBILITY OF THE PROFESSIONAL ENGINEER WHO PREPARED AND CERTIFIED THESE PLANS.

APPROVED THIS _____ DAY OF _____, 2020
DELAWARE COUNTY
SANITARY ENGINEER

APPROVED THIS _____ DAY OF _____, 2020
DELAWARE COUNTY
ENGINEER

APPROVED THIS _____ DAY OF _____, 2020
COUNTY COMMISSIONER

APPROVED THIS _____ DAY OF _____, 2020
COUNTY COMMISSIONER

APPROVED THIS _____ DAY OF _____, 2020
COUNTY COMMISSIONER


APPROVED BY LETTER:
OHIO ENVIRONMENTAL PROTECTION AGENCY
DATE : -

THIS IS TO CERTIFY THAT GOOD ENGINEERING PRACTICES HAVE BEEN UTILIZED IN THE DESIGN OF THIS PROJECT AND THAT ALL OF THE MINIMUM STANDARDS FOR DELAWARE COUNTY HAVE BEEN MET, INCLUDING THOSE STANDARDS GREATER THAN THE MINIMUM WHERE, IN MY OPINION, THEY ARE NEEDED TO PROTECT THE SAFETY OF THE PUBLIC. ANY VARIANCES TO THE ABOVE STANDARDS ARE CONSISTENT WITH SOUND ENGINEERING PRACTICES AND ARE NOT DETRIMENTAL TO THE PUBLIC SAFETY AND CONVENIENCE. THESE VARIANCES HAVE BEEN LISTED HEREIN AND HAVE BEEN APPROVED BY THE DELAWARE COUNTY SANITARY ENGINEER.

William D. Boggs
Registered Engineer

E-73937
Reg. No.

JULY 1, 2020
Date



P:\Projects\2018\20401WD - 185663 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal G-1 Legends & Symbols_R1.dwg Jul 01, 2020 - 2:36pm

	6	5	4	3	2	1																																																																																																																																																							
A	<div>ESTIMATED QUANTITIES TABLE</div> <table><tr><th>ITEM</th><th>QTY</th><th>UNIT</th><th>DESCRIPTION</th></tr><tr><td>108</td><td>1</td><td>LS</td><td>CONSTRUCTION LAYOUT STAKES</td></tr><tr><td>126</td><td>1</td><td>LS</td><td>TREE PROTECTION DURING CONSTRUCTION</td></tr><tr><td>201*</td><td>1</td><td>LS</td><td>CLEARING & GRUBBING</td></tr><tr><td>201*</td><td>7</td><td>EA</td><td>TREE REMOVED, 12-INCH</td></tr><tr><td>203</td><td>176</td><td>CY</td><td>AGGREGATE BASE</td></tr><tr><td>203*</td><td>9</td><td>CY</td><td>ROCK EXCAVATION</td></tr><tr><td>208</td><td>1,045</td><td>LF</td><td>8" SDR 35 SANITARY PIPE WITH TYPE A BEDDING</td></tr><tr><td>208</td><td>4,844</td><td>LF</td><td>8" SDR 35 SANITARY PIPE WITH TYPE B BEDDING</td></tr><tr><td>208</td><td>451</td><td>LF</td><td>8" C900 SANITARY PIPE W/TYPE A BEDDING</td></tr><tr><td>208</td><td>535</td><td>LF</td><td>12-INCH STORM PIPE WITH TYPE B BEDDING</td></tr><tr><td>208</td><td>61</td><td>LF</td><td>15-INCH STORM PIPE WITH TYPE B BEDDING</td></tr><tr><td>208</td><td>90</td><td>LF</td><td>6-INCH DIAMETER PIPE RISERS</td></tr><tr><td>208</td><td>56</td><td>EA</td><td>8-INCH X 6-INCH DIAMETER WYE FITTING</td></tr><tr><td>209</td><td>30</td><td>EA</td><td>MANHOLE</td></tr><tr><td>210</td><td>793</td><td>LF</td><td>2" HDPE SDR 9 PRESSURE SERVICE LINE & APPENDAGES</td></tr><tr><td>254*</td><td>2,434</td><td>SY</td><td>ASPHALT PLANING</td></tr><tr><td>301*</td><td>47</td><td>CY</td><td>ASPHALT CONCRETE BASE</td></tr><tr><td>303</td><td>1</td><td>LS</td><td>DEWATERING</td></tr><tr><td>314</td><td>39</td><td>CY</td><td>DRIVEWAY PAVEMENT, ASPHALT</td></tr><tr><td>314</td><td>76</td><td>CY</td><td>DRIVEWAY PAVEMENT, CONCRETE</td></tr><tr><td>314</td><td>4</td><td>CY</td><td>PERMANENT PAVEMENT REPLACEMENT, TYPE III</td></tr><tr><td>315</td><td>1</td><td>LS</td><td>TRAFFIC CONTROL</td></tr><tr><td>317</td><td>14,903</td><td>SY</td><td>SEEDING AND MULCHING, TYPE 3C</td></tr><tr><td>407*</td><td>203</td><td>GAL.</td><td>TACK COAT</td></tr><tr><td>408*</td><td>379</td><td>GAL.</td><td>PRIME COAT</td></tr><tr><td>412</td><td>2,710</td><td>LF</td><td>6-INCH DIAMETER PIPE, SANITARY HOUSE CONNECTION SERVICE</td></tr><tr><td>441*</td><td>114</td><td>CY</td><td>ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22</td></tr><tr><td>609*</td><td>6,300</td><td>LF</td><td>FILTER FABRIC FENCE</td></tr><tr><td>613*</td><td>15</td><td>CY</td><td>LOW STRENGTH MORTAR BACKFILL</td></tr><tr><td>616*</td><td>0.5</td><td>MGal</td><td>WATER</td></tr><tr><td>624*</td><td>1</td><td>LS</td><td>MOBILIZATION</td></tr><tr><td>661*</td><td>4</td><td>EA</td><td>DECIDUOUS TREE</td></tr><tr><td>670*</td><td>10</td><td>EA</td><td>INLET PROTECTION</td></tr><tr><td>SPEC</td><td>1</td><td>LS</td><td>LANDSCAPE RESTORATION</td></tr><tr><td>SPEC</td><td>1</td><td>LS</td><td>DEWATERING</td></tr><tr><td>SPEC</td><td>1</td><td>LS</td><td>DEL-CO WATER ALLOWANCE</td></tr></table> <div>* ITEM NUMBERS TAKEN FROM ODOT ITEM MASTER 2019</div>			ITEM	QTY	UNIT	DESCRIPTION	108	1	LS	CONSTRUCTION LAYOUT STAKES	126	1	LS	TREE PROTECTION DURING CONSTRUCTION	201*	1	LS	CLEARING & GRUBBING	201*	7	EA	TREE REMOVED, 12-INCH	203	176	CY	AGGREGATE BASE	203*	9	CY	ROCK EXCAVATION	208	1,045	LF	8" SDR 35 SANITARY PIPE WITH TYPE A BEDDING	208	4,844	LF	8" SDR 35 SANITARY PIPE WITH TYPE B BEDDING	208	451	LF	8" C900 SANITARY PIPE W/TYPE A BEDDING	208	535	LF	12-INCH STORM PIPE WITH TYPE B BEDDING	208	61	LF	15-INCH STORM PIPE WITH TYPE B BEDDING	208	90	LF	6-INCH DIAMETER PIPE RISERS	208	56	EA	8-INCH X 6-INCH DIAMETER WYE FITTING	209	30	EA	MANHOLE	210	793	LF	2" HDPE SDR 9 PRESSURE SERVICE LINE & APPENDAGES	254*	2,434	SY	ASPHALT PLANING	301*	47	CY	ASPHALT CONCRETE BASE	303	1	LS	DEWATERING	314	39	CY	DRIVEWAY PAVEMENT, ASPHALT	314	76	CY	DRIVEWAY PAVEMENT, CONCRETE	314	4	CY	PERMANENT PAVEMENT REPLACEMENT, TYPE III	315	1	LS	TRAFFIC CONTROL	317	14,903	SY	SEEDING AND MULCHING, TYPE 3C	407*	203	GAL.	TACK COAT	408*	379	GAL.	PRIME COAT	412	2,710	LF	6-INCH DIAMETER PIPE, SANITARY HOUSE CONNECTION SERVICE	441*	114	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	609*	6,300	LF	FILTER FABRIC FENCE	613*	15	CY	LOW STRENGTH MORTAR BACKFILL	616*	0.5	MGal	WATER	624*	1	LS	MOBILIZATION	661*	4	EA	DECIDUOUS TREE	670*	10	EA	INLET PROTECTION	SPEC	1	LS	LANDSCAPE RESTORATION	SPEC	1	LS	DEWATERING	SPEC	1	LS	DEL-CO WATER ALLOWANCE						
ITEM	QTY	UNIT	DESCRIPTION																																																																																																																																																										
108	1	LS	CONSTRUCTION LAYOUT STAKES																																																																																																																																																										
126	1	LS	TREE PROTECTION DURING CONSTRUCTION																																																																																																																																																										
201*	1	LS	CLEARING & GRUBBING																																																																																																																																																										
201*	7	EA	TREE REMOVED, 12-INCH																																																																																																																																																										
203	176	CY	AGGREGATE BASE																																																																																																																																																										
203*	9	CY	ROCK EXCAVATION																																																																																																																																																										
208	1,045	LF	8" SDR 35 SANITARY PIPE WITH TYPE A BEDDING																																																																																																																																																										
208	4,844	LF	8" SDR 35 SANITARY PIPE WITH TYPE B BEDDING																																																																																																																																																										
208	451	LF	8" C900 SANITARY PIPE W/TYPE A BEDDING																																																																																																																																																										
208	535	LF	12-INCH STORM PIPE WITH TYPE B BEDDING																																																																																																																																																										
208	61	LF	15-INCH STORM PIPE WITH TYPE B BEDDING																																																																																																																																																										
208	90	LF	6-INCH DIAMETER PIPE RISERS																																																																																																																																																										
208	56	EA	8-INCH X 6-INCH DIAMETER WYE FITTING																																																																																																																																																										
209	30	EA	MANHOLE																																																																																																																																																										
210	793	LF	2" HDPE SDR 9 PRESSURE SERVICE LINE & APPENDAGES																																																																																																																																																										
254*	2,434	SY	ASPHALT PLANING																																																																																																																																																										
301*	47	CY	ASPHALT CONCRETE BASE																																																																																																																																																										
303	1	LS	DEWATERING																																																																																																																																																										
314	39	CY	DRIVEWAY PAVEMENT, ASPHALT																																																																																																																																																										
314	76	CY	DRIVEWAY PAVEMENT, CONCRETE																																																																																																																																																										
314	4	CY	PERMANENT PAVEMENT REPLACEMENT, TYPE III																																																																																																																																																										
315	1	LS	TRAFFIC CONTROL																																																																																																																																																										
317	14,903	SY	SEEDING AND MULCHING, TYPE 3C																																																																																																																																																										
407*	203	GAL.	TACK COAT																																																																																																																																																										
408*	379	GAL.	PRIME COAT																																																																																																																																																										
412	2,710	LF	6-INCH DIAMETER PIPE, SANITARY HOUSE CONNECTION SERVICE																																																																																																																																																										
441*	114	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22																																																																																																																																																										
609*	6,300	LF	FILTER FABRIC FENCE																																																																																																																																																										
613*	15	CY	LOW STRENGTH MORTAR BACKFILL																																																																																																																																																										
616*	0.5	MGal	WATER																																																																																																																																																										
624*	1	LS	MOBILIZATION																																																																																																																																																										
661*	4	EA	DECIDUOUS TREE																																																																																																																																																										
670*	10	EA	INLET PROTECTION																																																																																																																																																										
SPEC	1	LS	LANDSCAPE RESTORATION																																																																																																																																																										
SPEC	1	LS	DEWATERING																																																																																																																																																										
SPEC	1	LS	DEL-CO WATER ALLOWANCE																																																																																																																																																										
B																																																																																																																																																													
C	<div>CONVENTIONAL LINETYPES & SYMBOLS</div> <div><div>COUNTY LINE</div><div>TOWNSHIP LINE</div><div>SECTION LINE</div><div>CORPORATION LINE</div><div>FENCE LINE (EX)</div><div>CENTER LINE</div><div>RIGHT OF WAY (EX)</div><div>RIGHT OF WAY (PR)</div><div>STANDARD HIGHWAY EASE.(EX)</div><div>TEMPORARY RIGHT OF WAY</div><div>CHANNEL EASE. (PR)</div><div>UTILITY EASE. (EX)</div><div>RAILROAD</div><div>GUARDRAIL (EX)</div><div>CONSTRUCTION LIMITS</div><div>EDGE OF PAVEMENT (EX)</div><div>EDGE OF PAVEMENT (PR)</div><div>EDGE OF SHOULDER (EX)</div><div>EDGE OF SHOULDER (PR)</div><div>DITCH/CREEK (EX)</div><div>DITCH/CREEK (PR)</div><div>TREE LINE (EX)</div><div>OWNERSHIP HOOK SYM</div><div>PROPERTY LINE SYM</div><div>BREAK LINE SYM</div></div> <div><div>TREE (PR)</div><div>TREE (EX)</div><div>SHRUB (EX)</div><div>TREE (REMOVE)</div><div>SHRUB (REMOVE)</div><div>EVERGREEN (EX)</div><div>STUMP</div><div>EVERGREEN (REMOVE)</div><div>STUMP (REMOVE)</div><div>WETLAND (PR)</div><div>GRASS (PR)</div><div>AERIAL TARGET</div><div>POST (EX)</div><div>MAILBOX (EX)</div><div>MAILBOX (PR)</div><div>LIGHT (EX)</div><div>TELEPHONE MARKER (EX)</div><div>FIRE HYDRANT (EX)</div><div>WATER METER (EX)</div><div>WATER VALVE (EX)</div><div>UTILITY VALVE UNKNOWN (EX.)</div><div>TELEPHONE POLE (EX)</div><div>POWER POLE (EX)</div><div>LIGHT POLE (EX)</div></div>																																																																																																																																																												
D																																																																																																																																																													
E	6	5	4	3	2	1																																																																																																																																																							

DRAWING INDEX	
SHEET #	SHEET TITLE
G-0	COVER
G-1	LEGEND & SYMBOLS, DRAWING INDEX, LATERAL TABLE & ESTIMATED QUANTITIES
G-2	GENERAL NOTES
G-3	STORM WATER DETAILS -- EROSION CONTROL NOTES
G-4	STORM WATER DETAILS -- EROSION CONTROL NOTES
G-5	MISCELLANEOUS DETAILS
G-6	MISCELLANEOUS DETAILS
G-7	MISCELLANEOUS DETAILS
G-8	MISCELLANEOUS DETAILS
G-9	EROSION & SEDIMENT CONTROL DETAILS
C-1	PLAN & PROFILE -- ERIN WOODS -- STA. 0+00 to STA. 10+00
C-2	PLAN & PROFILE -- ERIN WOODS -- STA. 10+00 to STA. 18+00
C-3	PLAN & PROFILE -- ERIN WOODS -- STA. 18+00 to STA. 27+00
C-4	PLAN & PROFILE -- ERIN WOODS -- STA. 27+00 to STA. 34+95
C-5	PLAN & PROFILE -- SYLVIAN DR & SERENITY DR -- STA. 40+00 to STA. 50+00
C-6	PLAN & PROFILE -- COMMON ACCESS DR -- STA. 50+00 to STA. 57+45
C-7	PLAN & PROFILE -- SYLVIAN DR -- STA. 60+00 to STA. 64+00 & STA. 70+00 to STA. 74+26
C-8	PLAN & PROFILE -- SERENITY -- STA. 80+00 to STA. 82+74
MT-1	MAINTENANCE OF TRAFFIC NOTES
MT-2	MAINTENANCE OF TRAFFIC NOTES & DETAILS
MT-3	MAINTENANCE OF TRAFFIC DETAILS

SANITARY SEWER LATERAL TABLE										
ADDRESS	STATION	MAIN CL. ELEVATION	LATERAL SLOPE: 0.0208		EOS ELEVATION	EOS GRADE	EOS DEPTH w/o RISER	RISER LENGTH (FT) (APPROX.)	GRINDER PUMP	SHT #
			LATERAL START ELEVATION	LATERAL LENGTH (FT)						
7839 HARRIOTT RD.	01+00.00	918.13	918.63	42	919.49	937.25	17.76	6	N	C-1
7801 HARRIOTT RD.	02+32.00	918.67	919.17	42	920.03	941.95	21.92	10	N	C-1
7769 HARRIOTT RD.	04+27.00	919.54	920.04	42	920.90	940.91	20.01	9	N	C-1
9716 ERIN WOODS DR.	05+81.00	920.16	920.66	42	921.52	937.74	16.22	5	N	C-1
9750 ERIN WOODS DR.	10+21.00	922.13	922.63	* 72	924.12	925.82	1.70	0	Y	C-2
9719 ERIN WOODS DR.	10+31.00	922.17	922.67	* 89	924.51	925.15	0.64	0	Y	C-2
7639 HARRIOTT RD.	10+51.00	922.24	922.74	** 240	927.72	931.04	3.32	0	N/A***	C-2
9776 ERIN WOODS DR.	11+68.00	922.72	923.22	* 27	923.77	920.90	-2.87	0	Y	C-2
9761 ERIN WOODS DR.	12+51.00	923.15	923.65	* 71	925.12	921.58	-3.54	0	Y	C-2
9808 ERIN WOODS DR.	13+72.00	924.38	924.88	81	926.55	938.30	11.75	0	N	C-2
9787 ERIN WOODS DR.	14+00.00	924.77	925.27	25	925.78	936.87	11.09	0	N	C-2
9817 ERIN WOODS DR.	14+79.00	925.85	926.35	23	926.82	938.17	11.35	0	N	C-2
9845 ERIN WOODS DR.	15+93.00	926.54	927.04	24	927.53	942.84	15.31	4	N	C-2
9846 ERIN WOODS DR.	17+33.00	927.2	927.7	81	929.37	948.77	19.40	8	N	C-2
9877 ERIN WOODS DR.	18+33.00	927.67	928.17	28	928.74	948.37	19.63	8	N	C-3
9882 ERIN WOODS DR.	18+84.00	927.97	928.47	83	930.19	949.68	19.49	8	N	C-3
9904 ERIN WOODS DR.	21+14.00	930.63	931.13	82	932.83	949.79	16.96	5	N	C-3
9937 ERIN WOODS DR.	22+22.00	934.42	934.92	22	935.37	948.10	12.73	1	N	C-3
9930 ERIN WOODS DR.	22+80.00	936.44	936.94	72	938.43	948.20	9.77	0	N	C-3
9971 ERIN WOODS DR.	24+34.00	938.04	938.54	22	938.99	947.00	8.01	0	N	C-3
9956 ERIN WOODS DR.	24+42.00	938.1	938.6	72	940.09	948.60	8.51	0	N	C-3
9980 ERIN WOODS DR.	24+70.00	938.29	938.79	72	940.28	948.50	8.22	0	N	C-3
9989 ERIN WOODS DR.	25+87.00	939.09	939.59	22	940.04	949.44	9.40	0	N	C-3
10002 ERIN WOODS DR.	26+39.00	939.54	940.04	72	941.53	954.00	12.47	1	N	C-3
10222 SYLVIAN DR.	27+95.00	940.69	941.19	72	942.68	955.90	13.22	2	N	C-4
10201 SYLVIAN DR.	29+66.00	942.42	942.92	71	944.39	958.10	13.71	2	N	C-4
10225 SYLVIAN DR.	30+18.00	943.16	943.66	71	945.13	958.20	13.07	2	N	C-4
10251 SYLVIAN DR.	31+97.00	945.74	946.24	70	947.69	958.20	10.51	0	N	C-4
10266 SYLVIAN DR.	32+21.00	946.13	946.63	24	947.12	956.50	9.38	0	N	C-4
10275 SYLVIAN DR.	34+04.00	948.77	949.27	115	951.65	962.45	10.80	0	N	C-4
10291 SYLVIAN DR.	34+26.00	949.08	949.58	99	951.63	959.60	7.97	0	N	C-4
10288 SYLVIAN DR.	34+75.00	949.79	950.29	28	950.86	959.40	8.54	0	N	C-4
9913 ERIN WOODS DR.	40+41.00	928.92	929.42	36	930.16	945.92	15.76	4	N	C-5
9961 SYLVIAN DR.	43+27.00	930.09	930.59	* 79	932.22	941.09	8.87	0	Y	C-5
9955 SYLVIAN DR.	43+79.00	930.43	930.93	56	932.08	945.49	13.41	2	N	C-5
9979 SYLVIAN DR.	44+92.00	931.47	931.97	82	933.67	944.15	10.48	0	N	C-5
7650 SERENITY DR.	45+82.00	932.14	932.64	99	934.69	946.78	12.09	1	N	C-5
9990 SYLVIAN DR.	45+93.00	932.18	932.68	32	933.34	950.20	16.86	5	N	C-5
7673 SERENITY DR.	51+25.00	934.61	935.11	27	935.66	943.95	8.29	0	N	C-6
7655 SERENITY DR.	51+55.00	934.74	935.24	68	936.64	947.78	11.14	0	N	C-6
7669 SERENITY DR.	54+28.00	938.57	939.07	22	939.52	949.35	9.83	0	N	C-6
7661 SERENITY DR.	55+19.00	939.52	940.02	74	941.55	949.61	8.06	0	N	C-6
7665 SERENITY DR.	57+23.00	941.69	942.19	38	942.97	950.00	7.03	0	N	C-6
10174 SYLVIAN DR.	61+43.00	942.28	942.78	21	943.21	953.09	9.88	0	N	C-7
10177 SYLVIAN DR.	61+92.00	942.51	943.01	74	944.54	951.80	7.26	0	N	C-7
10151 SYLVIAN DR.	63+40.00	943.19	943.69	75	945.24	954.10	8.86	0	N	C-7
10125 SYLVIAN DR.	63+85.00	943.4	943.9	68	945.30	953.14	7.84	0	N	C-7
10036 SYLVIAN DR.	70+26.00	934.95	935.45	25	935.96	953.59	17.63	6	N	C-7
10070 SYLVIAN DR.	72+58.00	938.55	939.05	32	939.71	950.20	10.49	0	N	C-7
10069 SYLVIAN DR.	73+63.00	940.14	940.64	97	942.65	952.23	9.58	0	N	C-7
10120 SYLVIAN DR.	74+03.00	940.75	941.25	32	941.91	951.02	9.11	0	N	C-7
10099 SYLVIAN DR.	74+16.00	940.94	941.44	98	943.47	950.08	6.61	0	N	C-7
7664 SERENITY DR.	80+10.00	934.32	934.82	76	936.39	946.00	9.61	0	N	C-8
7670 SERENITY DR.	81+56.00	935.06	935.56	79	937.19	942.35	5.16	0	N	C-8
7690 SERENITY DR.	82+53.00	935.56	936.06	* 109	938.32	950.52	12.20	1	Y	C-8
7694 SERENITY DR.	82+64.00	935.61	936.11	* 106	938.30	941.00	2.70	0	N/A***	C-8

SANITARY LATERALS CALCULATED AT 2.08% SLOPE
RISER LENGTHS CALCULATED BASED ON 45 DEGREE CONNECTION ANGLE OF WYE AT MAIN.
* LATERAL TO BE PRESSURE SERVICE LINE INSTALLED PER DCRSD STD. DETAIL Sa.S-31
** LATERAL TO BE 2" HDPE SDR 9 PRESSURE SERVICE LINE INSTALLED PER DCRSD STD. DETAIL Sa.S-31
*** N/A NO RESIDENCE AT THIS ADDRESS AT THE TIME OF DESIGN.

DELaware COUNTY REGIONAL SEWER DISTRICT		CHECKED: JS	DATE: JULY 2020
DESIGNED: WDB			



DELAWARE COUNTY
REGIONAL SEWER DISTRICT

LEGEND & SYMBOLS,
DRAWING INDEX &
LATERAL TABLE &
ESTIMATED QUANTITIES

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

G - 1

P:\Projects\2018\201801-WD-18563 Woods of Glen Erin Delaware County\05 CADD - Drawings\Sheet90 Submittal\G-3&4 SWPPP R1 Notes.dwg Jul 01, 2020 - 7:16am

	6	5	4	3	2	1	
A	STORMWATER POLLUTION PREVENTION (SWPPP)						A
B	<div>PLAN DESIGNER: PRIME AE GROUP 8415 PULSAR PLACE, SUITE 300 COLUMBUS, OHIO 43240 PHONE: 614-839-0250</div> <div>PROJECT NAME: WOODS OF GLEN ERIN SANITARY IMPROVEMENTS</div> <div>PROJECT LOCATION: CONCORD TOWNSHIP, DELAWARE COUNTY, OHIO</div> <div>OWNER: DELAWARE COUNTY REGIONAL SEWER DISTRICT (DCRSD) 50 CHANNING STREET, 2ND FLOOR DELAWARE, OHIO 43015 PHONE: 740-833-2240 DCRSD PROJECT MANAGER: JULIE MCGILL EMAIL: JMCGILL@CO.DELAWARE.OH.US</div> <div>TOTAL ACRES DISTURBED: 1.44 ACRES</div> <div>1. SITE INFORMATION 1.1. INSTALLATION OF 6,340 FEET OF 8" SANITARY SEWER BY PIPE IN TRENCH (OPEN CUT). INSTALLATION OF 30 MANHOLE STRUCTURES. 1.2. SOIL DISTURBING ACTIVITIES WILL INCLUDE CLEARING AND GRUBBING, EXCAVATION, BACKFILL AND FINAL GRADING.</div> <div>2. SEQUENCE OF MAJOR ACTIVITIES 2.1. SILT FENCE SHALL BE INSTALLED PRIOR TO CLEARING OR GRADING ANY PORTIONS OF THE SITE. AREAS WHERE CONSTRUCTION CEASES FOR MORE THAN 21 DAYS SHALL BE STABILIZED WITH A TEMPORARY SEED AND MULCH WITHIN 7 DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA, THAT AREA WILL BE STABILIZED WITH PERMANENT SEED AND MULCH.</div> <div>3. NAME OF RECEIVING WATERS 3.1. THE SITE DRAINS INTO AN UNNAMED TRIBUTARIES OF THE SCIOTO RIVER</div> <div>4. EROSION AND SEDIMENT CONTROL GENERAL NOTES 4.1. STOCKPILED TOPSOIL AND EXCAVATED MATERIAL IS TO BE PROTECTED THROUGH THE USE OF TEMPORARY AND PERMANENT SEEDING, OR COVERED WITH ANCHORED STRAW MULCH. 4.2. FINAL GRADING WILL BE CONSISTENT WITH PRE-CONSTRUCTION TOPOGRAPHY TO MAINTAIN DRAINAGE AND AESTHETICS. 4.3. REMOVE ONLY THOSE TREES, SHRUBS, AND GRASSES THAT MUST BE REMOVED TO PERMIT ACTUAL CONSTRUCTION. PROTECT THE REMAINING TO PRESERVE THEIR AESTHETIC AND EROSION CONTROL VALUE. 4.4. ALL EROSION/SEDIMENT/DUST CONTROL PRACTICES SHALL BE PERFORMED AS DIRECTED BY THE ODNR PUBLICATION "RAINWATER AND LAND DEVELOPMENT", CURRENT EDITION. EROSION CONTROL DEVICES ARE TO BE MAINTAINED IN EFFECTIVE WORKING CONDITION DURING CONSTRUCTION AND UNTIL THE CONSTRUCTION AREA HAS BEEN PERMANENTLY STABILIZED. 4.5. BACKFILL TRENCHES IMMEDIATELY AFTER COMPACTION. SEED AND MULCH TRENCHES WITHIN 7 DAYS AFTER TRENCHES ARE OPENED. 4.6. SILT FROM CONSTRUCTION OPERATIONS SHALL NOT BE PERMITTED TO ENTER THE STORM DRAIN SYSTEM OR WATERWAYS (NATURAL OR MAN-MADE OR ADJACENT PRIVATE PROPERTY). CONSTRUCTION OCCURRING NEAR STORM DRAIN INLETS OR WATERWAYS (NATURAL OR MAN-MADE), SHALL REQUIRE EROSION CONTROL MEASURES, SUCH AS SILT FENCE AND STRAW BALES BARRIERS, TO PREVENT SILT FROM ENTERING THE STORM DRAIN AND WATERWAYS (NATURAL OR MAN-MADE OR ADJACENT PRIVATE PROPERTY). 4.7. TIMING OF SEDIMENT – TRAPPING PRACTICES 4.7.1. SEDIMENT CONTROL PRACTICES SHALL BE FUNCTIONAL THROUGHOUT EARTH DISTURBING ACTIVITY. SETTLING FACILITIES, PERIMETER CONTROLS AND OTHER PRACTICES INTENDED TO TRAP SEDIMENT SHALL BE IMPLEMENTED AS THE FIRST STEP OF GRADING OR CONSTRUCTION AND WITHIN SEVEN DAYS FROM THE, START OF GRUBBING. THEY SHALL CONTINUE TO FUNCTION UNTIL THE UPSLOPE DEVELOPMENT AREA IS RE-STABILIZED. THESE CONTROLS SHALL BE SELECTED AND LOCATED AS DIRECTED BY THE ENGINEER. 4.8. STABILIZATION OF DENUDED AREAS 4.8.1. DENUDED AREAS SHALL HAVE SOIL STABILIZATION APPLIED WITHIN SEVEN DAYS OF DISTURBANCE IF THEY ARE TO REMAIN SUBSTANTIALLY UNWORKED FOR MORE THAN 21 DAYS. PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE, AND SHALL ALSO BE APPLIED WITHIN SEVEN DAYS TO DENUDED AREAS WHICH MAY NOT BE AT FINAL GRADE, BUT WHICH WILL REMAIN DORMANT (UNDISTURBED) FOR LONGER THAN 21 DAYS. 4.9. SEDIMENT BARRIERS 4.9.1. SHEET FLOW RUNOFF FROM DENUDED AREAS SHALL BE FILTERED OR DIVERTED TO A SETTLING FACILITY. ADDITIONAL CONTROLS MAY BE SELECTED AND INSTALLED AS DIRECTED BY THE ENGINEER.</div> <div>4.10. STORM WATER INLET PROTECTION 4.10.1. ALL STORM SEWER INLETS WHICH ACCEPT WATER RUNOFF FROM THE PROJECT AREA SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER WILL NOT ENTER THE STORM SEWER SYSTEMS WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT, UNLESS THE STORM SEWER SYSTEM DRAINS TO A SETTLING FACILITY. THESE CONTROLS SHALL BE SELECTED AND LOCATED AS DIRECTED BY THE ENGINEER. 4.11. SLOUGHING AND DUMPING 4.11.1. NO SOIL, ROCK, DEBRIS OR ANY OTHER MATERIAL SHALL BE DUMPED OR PLACED INTO A WATER RESOURCE OR INTO SUCH PROXIMITY THAT IT MAY READILY SLOUGH, SLIP, OR ERODE INTO A WATER RESOURCE UNLESS SUCH DUMPING OR PLACING IS AUTHORIZED BY THE ENGINEER. UNSTABLE SOILS PRONE TO SLIPPING OR LANDSLIDING SHALL NOT BE GRADED, EXCAVATED, FILLED OR HAVE LOADS IMPOSED UPON THEM UNLESS THE WORK IS AUTHORIZED BY THE ENGINEER. 4.12. ESTABLISHMENT OF PERMANENT VEGETATION 4.12.1 PERMANENT VEGETATON SHALL NOT BE CONSIDERED ESTABLISHED UNTIL GROUND COVER IS ACHIEVED WHICH, IN THE OPINION OF THE ENGINEER, PROVIDES ADEQUATE COVER AND IS MATURE ENOUGH TO CONTROL SOIL EROSION SATISFACTORILY AND TO SURVIVE ADVERSE WEATHER CONDITIONS. 4.13 MAINTENANCE 4.13.1 ALL SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED TO MINIMIZE MAINTENANCE REQUIREMENTS. THEY SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE CONTINUED MAINTENANCE OF ALL EROSION CONTROLS DURING THE LIFE OF THE PROJECT. 4.14 DETAILS HAVE BEEN SHOWN ON THE PLAN IN AN EFFORT TO HELP THE CONTRACTOR PROVIDE EROSION AND SEDIMENTATION CONTROL. THE DETAILS SHOWN ON THE PLAN SHALL BE CONSIDERED A MINIMUM. ADDITIONAL OR ALTERNATE DETAILS MAY BE FOUND IN THE ODNR MANUAL: "RAINWATER AND LAND DEVELOPMENT", LATEST EDITION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING NECESSARY AND ADEQUATE MEASURES FOR PROPER CONTROL FOR EROSION AND SEDIMENT RUNOFF FROM THE CONSTRUCTION AREAS, SUBJECT TO APPROVAL FROM THE ENGINEER.</div> <div>5. EROSION AND SEDIMENT CONTROLS 5.1. TEMPORARY STABILIZATION 5.1.1. TOP SOIL STOCKPILES AND DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR AT LEAST 15 DAYS WILL BE IMMEDIATELY GRADED AND CLEANED UP SO AS NOT TO APPEAR DISHEVELED OR AN EYESORE. STABILIZED WITH TEMPORARY SEED AND MULCH NO LATER THAN 7 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT AREA. THE TEMPORARY SEED, AGRICULTURAL LIMESTONE AND FERTILIZER SHALL BE APPLIED ACCORDING TO THE RATES STATED IN DCRSD CMS ITEM 317. ALL AREAS NOT UNDER IMMEDIATE CONSTRUCTION SHALL BE KEPT NEAT. WASHOUTS SHALL BE FIXED IMMEDIATELY AND IN A SAFE MANNER. ROADSIDE DITCHES AND DRAINAGE STRUCTURES SHALL BE OPERABLE IMMEDIATELY AFTER CONSTRUCTION. ALL SEDIMENT AND EROSION CONTROL REQUIREMENTS APPLY. 5.2. PERMANENT STABILIZATION 5.2.1. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASES SHALL BE STABILIZED WITH PERMANENT SEED NO LATER THAN 7 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY. THE PERMANENT SEED MIX, AGRICULTURAL LIMESTONE AND FERTILIZER SHALL BE APPLIED ACCORDING TO THE RATES STATED IN DCRSD CMS ITEM 317. 5.2.2. THE FOLLOWING SHALL APPLY IF WORK IS PERFORMED OUTSIDE OF NORMAL GROWING SEASON. BETWEEN OCTOBER 1 AND NOVEMBER 20 WHEN SOIL CONDITIONS PERMIT, PERMANENT SEEDING AREAS MAY BE PREPARED WITH LIME AND FERTILIZER BUT SHALL BE MULCHED AND ANCHORED WITHOUT SEEDING. AFTER NOVEMBER 20 AND BEFORE MARCH 15, BROADCAST RECOMMENDED SEED MIXTURE AT 150% OF RECOMMENDED RATES (CONSIDERED DORMANT SEEDING RATES) 5.3. STRUCTURAL CONTROLS 5.3.1. SILT FENCE SHALL BE CONSTRUCTED AS INDICATED ON THE STORM WATER POLLUTION PREVENTION PLAN. SILT FENCING SHALL BE OF A TYPE AS INDICATED IN THE SPECIFICATIONS AND SHALL BE INSTALLED AS SOON AS THE AREAS ARE CLEARED IN WHICH THE FENCE IS DESIGNATED TO BE INSTALLED. SILT FENCE SHALL BE INSTALLED AT THE TOP OF ALL SLOPES AND SHALL BE PLACED SUCH THAT NO WATER CAN FLOW AS A CONCENTRATED STREAM. IF AFTER THE INSTALLATION OF THE SILT FENCE, CONCENTRATED FLOWS OCCUR OR WATER BYPASSES THE FENCE, ADDITIONAL MEASURES SHALL BE INSTALLED OR THE EXISTING MEASURES SHALL BE MODIFIED AT THE DIRECTION OF THE ENGINEER. 5.4. STORM WATER MANAGEMENT 5.4.1. STORM WATER DRAINAGE WILL BE PROVIDED BY THE CURRENT DRAINAGE PATTERNS OF THE SITE. ADDITIONALLY, SILT FENCING ALONG THE PERIMETER OF THE SITE WILL DIRECT AND DIFFUSE RUNOFF WHILE CAPTURING ANY SEDIMENT CONTAINED IN THE RUNOFF.</div> <div>6. OTHER CONTROLS 6.1. WASTE MATERIALS 6.1.1. ALL CONSTRUCTION WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED A MINIMUM OF ONCE PER WEEK OR MORE OFTEN IF NECESSARY, AND THE TRASH WILL BE HAULED TO AN OEPA APPROVED C AND DD LANDFILL AREA. NO CONSTRUCTION WASTE MATERIALS WILL BE BURIED ONSITE. ALL PERSONNEL WILL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL NOTICES STATING THESE PRACTICES WILL BE POSTED IN THE OFFICE TRAILER AND THE CONTRACTOR(S) WILL BE RESPONSIBLE FOR SEEING THAT THESE PROCEDURES ARE FOLLOWED. 6.2. HAZARDOUS MATERIALS 6.2.1. ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PRACTICES AND THE CONTRACTOR(S) WILL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED.</div> <div>7. TIMING OF CONTROLS/MEASURES 7.1. AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, THE EROSION AND SEDIMENT CONTROLS WILL BE CONSTRUCTED PRIOR TO CLEARING OR GRADING OF THE SITE AND SHALL BE FUNCTIONAL THROUGHOUT ALL EARTH DISTURBING ACTIVITIES. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 21 DAYS WILL BE STABILIZED WITH TEMPORARY SEED AND MULCH WITHIN 7 DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA, THAT AREA WILL BE STABILIZED WITH PERMANENT SEED AND MULCH. ONLY AFTER THE ENTIRE SITE IS STABILIZED WILL THE EROSION AND SEDIMENT CONTROLS BE REMOVED.</div> <div>8. CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS 8.1. THE STORM WATER POLLUTION PREVENTION PLAN REFLECTS THE REQUIREMENTS FOR STORM WATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL, AS ESTABLISHED BY THE OHIO ENVIRONMENTAL PROTECTION AGENCY. TO ENSURE COMPLIANCE, THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE RAINWATER AND LAND DEVELOPMENT, OHIO'S STANDARDS FOR STORMWATER MANAGEMENT – LAND DEVELOPMENT AND URBAN STREAM PROTECTION". LATEST EDITION PUBLISHED BY THE OHIO DEPARTMENT OF NATURAL RESOURCES. THERE ARE NO OTHER LOCAL, STATE OR FEDERAL REQUIREMENTS FOR SEDIMENT AND EROSION SITE PLANS (OR PERMITS), OR STORM WATER MANAGEMENT SITE PLANS (OR PERMITS).</div> <div>9. MAINTENANCE/INSPECTION PROCEDURES 9.1. THESE ARE THE INSPECTION AND MAINTENANCE PRACTICES THAT WILL BE USED TO MAINTAIN EROSION AND SEDIMENT CONTROLS. 9.1.1. PARKING AREAS MAY REQUIRE PERIODIC TOP DRESSING WITH NEW GRAVEL. SEEDED AREAS ADJACENT TO THE ROADS AND PARKING AREAS SHOULD BE CHECKED PERIODICALLY TO ENSURE THAT A VIGOROUS STAND OF VEGETATION IS MAINTAINED. ROADSIDE DITCHES AND OTHER DRAINAGE STRUCTURES SHOULD BE CHECKED REGULARLY TO ENSURE THAT THEY DO NOT BECOME CLOGGED WITH SILT OR OTHER DEBRIS. 9.1.2. ALL CONTROL MEASURES WILL BE INSPECTED AT LEAST ONCE A WEEK AND FOLLOWING ANY STORM EVENT OF 0.5 INCHES OR GREATER. 9.1.3. ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF A REPAIR IS NECESSARY, IT WILL BE INITIATED WITHIN 24 HOURS OF REPORT. 9.1.4. BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCE WHEN IT HAS REACHED ONE-THIRD THE HEIGHT OF THE FENCE. ANY SEDIMENT DEPOSITS REMAINING IN-PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED. 9.1.5. SILT FENCE WILL BE INSPECTED FOR DEPTH OF SEDIMENT AND TEARS TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POST, AND TO SEE THAT THE FENCE POSTS ARE FIRMLY IN THE GROUND. 9.1.6 ALL TEMPORARY AND PERMANENT CONTROL PRACTICES SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ENSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL SEDIMENT CONTROL PRACTICES MUST BE MAINTAINED IN A FUNCTIONAL CONDITION UNTIL ALL UPSLOPE AREAS THEY CONTROL ARE PERMANENTLY STABILIZED. THE SWP3 SHALL BE DESIGNED TO MINIMIZE MAINTENANCE REQUIREMENTS. THE APPLICANT SHALL PROVIDE A DESCRIPTION OF MAINTENANCE PROCEDURES NEEDED TO ENSURE THE CONTINUED PERFORMANCE OF CONTROL PRACTICES. 9.1.7 THE CONTRACTOR SHALL INSTALL SILT FENCE AND SUITABLE EROSION CONTROL AROUND SOIL STOCKPILES AND MAINTAIN ALL EROSION CONTROL UNTIL NO OTHER EXCESS SOILS ARE EXPECTED. THE AREA HAS BEEN SEEDED AND MULCHED, AND THE THREAT OF EROSION HAS PASSED. 9.1.8 TEMPORARY AND PERMANENT SEEDING AND PLANTING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS AND HEALTHY GROWTH. 9.1.9 A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION, CONTRACTOR SHALL BE RESPONSIBLE FOR DESIGNATING INDIVIDUALS TO BE RESPONSIBLE FOR INSPECTING AND MAINTAINING ALL EROSION AND SEDIMENT CONTROLS. THESE INDIVIDUALS SHALL BE RESPONSIBLE FOR FILLING OUT INSPECTION AND MAINTENANCE REPORTS. 9.1.10 PERSONNEL SELECTED FOR INSPECTION AND MAINTENANCE DUTIES SHALL BE INSTRUCTED AS TO THE ACTIONS NECESSARY TO MAINTAIN PROPER EROSION AND SEDIMENT CONTROLS ON THE SITE.</div>						B
C	<div>DELTAWARE COUNTY REGIONAL SEWER DISTRICT</div> <div>DESIGNED: WJB DRAWN: MMB</div> <div>CHECKED: AS REVIEWED: RH</div> <div>DATE: JULY 2020</div>						C
D	<div>STORM WATER DETAILS EROSION CONTROL NOTES</div> <div>WOODS OF GLEN ERIN SANITARY SEWER IMPROVEMENTS</div>						D
E	<div>REVISION</div> <div>DATE</div>						E
	6	5	4	3	2	1	



DELTAWARE COUNTY
REGIONAL SEWER DISTRICT

STORM WATER DETAILS
EROSION CONTROL NOTES

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

G-3

P:\Projects\2018\2040-WD-16563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\G-3&4 SWPPP_R1 Notes.dwg Jul 01, 2020 - 7:18am

		6	5	4	3	2	1		
		STORMWATER POLLUTION PREVENTION (SWPPP)							
A	10. NON-STORM WATER DISCHARGES 10.1. IT IS EXPECTED THAT THE FOLLOWING NON-STORM WATER DISCHARGES WILL OCCUR FROM THE SITE DURING THE CONSTRUCTION PERIOD: 10.1.1. PAVEMENT WASH WATERS (WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED) 10.1.2. UNCONTAMINATED GROUNDWATER (FROM DEWATERING EXCAVATION). 10.2. ALL NON-STORM WATER DISCHARGES WILL BE DIRECTED TO PROTECTED INLETS OR SEDIMENT CONTROL DEVICES PRIOR TO DISCHARGE 11. INVENTORY FOR POLLUTION PREVENTION PLAN 11.1. THE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED TO BE PRESENT ONSITE DURING CONSTRUCTION: 11.1.1. CONCRETE 11.1.2. PETROLEUM BASED PRODUCTS 12. SPILL PREVENTION 12.1. MATERIAL MANAGEMENT PRACTICES 12.1.1. THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF. 12.2. GOOD HOUSEKEEPING 12.2.1. THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ONSITE DURING THE CONSTRUCTION PROJECT. 12.2.1.1. AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB. 12.2.1.2. ALL MATERIALS STORED ONSITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE. 12.2.1.3. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL. 12.2.1.4. SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER. 12.2.1.5. WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER. 12.2.1.6. MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED. 12.2.1.7. THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ONSITE. 12.3. HAZARDOUS PRODUCTS 12.3.1. THESE PRACTICES ARE USED TO REDUCE THE RISK ASSOCIATED WITH HAZARDOUS MATERIALS. 12.3.1.1. PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE 12.3.1.2. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY CONTAIN IMPORTANT PRODUCT INFORMATION. 12.3.1.3. IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED. 12.4. PRODUCT SPECIFIC PRACTICES 12.4.1. THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ONSITE: 12.4.1.1. PETROLEUM PRODUCTS 12.4.1.1.1. ALL ONSITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS. 13. SPILL CONTROL PRACTICES 13.1. IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: 13.1.1. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES. 13.1.2. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ONSITE. EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. 13.1.3. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. 13.1.4. THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE. 13.1.5. SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE. 13.1.6. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.		13.1.7. THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. HE WILL DESIGNATE AT LEAST THREE OTHER SITE PERSONNEL WHO WILL RECEIVE SPILL PREVENTION AND CLEANUP TRAINING. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF THE RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN THE MATERIAL STORAGE AREA AND IN THE OFFICE TRAILER ONSITE. 14. PROHIBITED CONSTRUCTION ACTIVITIES 14.1. THE CONTRACTOR SHALL NOT USE CONSTRUCTION PROCEEDINGS, ACTIVITIES OR OPERATIONS THAT MAY UNNECESSARILY IMPACT THE NATURAL ENVIRONMENT OR THE PUBLIC HEALTH AND SAFETY. PROHIBITED CONSTRUCTION PROCEDURES, ACTIVITIES OR OPERATIONS INCLUDE BUT ARE NOT LIMITED TO: 14.1.1. DISPOSING OF EXCESS OR UNSUITABLE EXCAVATED MATERIAL IN WETLANDS OR FLOOD PLAINS EVEN WITH THE PERMISSION OF THE PROPERTY OWNER. 14.1.2. INDISCRIMINATE, ARBITRARY, OR CAPRICIOUS OPERATION OF EQUIPMENT IN ANY STREAM CORRIDORS, ANY WETLANDS, ANY SURFACE WATERS, OR OUTSIDE THE EASEMENT LIMITS. 14.1.3. PUMPING OF SEDIMENT-LADEN WATER FROM TRENCHES OR OTHER EXCAVATIONS INTO ANY SURFACE WATERS, ANY STREAM CORRIDORS, ANY WETLANDS, AND STORM DRAINS OR COMBINED SEWERS. 14.1.4. DISCHARGING POLLUTANTS SUCH AS CHEMICALS, FUELS, LUBRICANTS, BITUMINOUS MATERIALS, RAW SEWAGE AND OTHER HARMFUL WASTE INTO OR ALONGSIDE OF RIVERS, STREAMS, IMPOUNDMENTS OR INTO NATURAL OR MAN-MADE CHANNELS LEADING THERETO. 14.1.5. PERMANENT OR UNSPECIFIED ALTERATION OF THE FLOW LINE OF THE STREAM. 14.1.6. DAMAGING VEGETATION OUTSIDE OF THE CONSTRUCTION AREA. 14.1.7. DISPOSAL OF TREES, BRUSH AND OTHER DEBRIS IN ANY STREAM CORRIDORS, ANY WETLANDS, ANY SURFACE WATERS, OR AT UNSPECIFIED LOCATIONS. 14.1.8. OPEN BURNING OF PROJECT DEBRIS WITHOUT A PERMIT. 14.1.9. STORING CONSTRUCTION EQUIPMENT AND VEHICLES AND/OR STOCKPILING CONSTRUCTION MATERIALS ON PROPERTY, PUBLIC OR PRIVATE, NOT PREVIOUSLY SPECIFIED BY THE ENGINEER FOR SAID PROJECT. 14.1.10. USING ANY SUBSTANCE OTHER THAN WATER TO CONTROL DUST. 15. SILT FENCE NOTES 15.1. SILT FENCING SHALL UTILIZE STANDARD STRENGTH OR EXTRA STRENGTH SYNTHETIC FILTER FABRICS. IT IS INTENDED TO BE USED FOR SITUATIONS IN WHICH ONLY SHEET OR OVERLAND FLOWS ARE EXPECTED. 15.1.1. SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS. 15.1.2. ALL SILT FENCE SHALL BE PLACED AS CLOSE TO THE CONTOUR AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS WHICH MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH. 15.1.3. TO PREVENT WATER PONDED BY THE SILT FENCE FROM FLOWING AROUND THE ENDS, EACH END SHALL BE CONSTRUCTED UPSLOPE SO THAT THE ENDS ARE AT A HIGHER ELEVATION. 15.1.4. WHERE POSSIBLE, SILT FENCE SHALL BE PLACED ON THE FLATTEST AREA AVAILABLE. 15.1.5. WHERE POSSIBLE, VEGETATION SHALL BE PRESERVED FOR 5 FT. (OR AS MUCH AS POSSIBLE) UPSLOPE FROM THE SILT FENCE. IF VEGETATION IS REMOVED, IT SHALL BE REESTABLISHED WITHIN 7 WORKING DAYS FROM THE INSTALLATION OF THE SILT FENCE. 15.1.6. THE SILT FENCE SHALL BE PLACED IN A TRENCH CUT A MINIMUM OF 6 IN. DEEP. THE TRENCH SHALL BE CUT WITH A TRENCHER, CABLE LAYING MACHINE, OR OTHER SUITABLE DEVICE WHICH WILL ENSURE AN ADEQUATELY UNIFORM TRENCH DEPTH. 15.1.7. THE SILT FENCE SHALL BE PLACED WITH THE STAKES ON THE DOWNSLOPE SIDE OF THE GEOTEXTILE AND SO THAT 8 IN. OF CLOTH ARE BELOW THE GROUND SURFACE. EXCESS MATERIAL SHALL LAY ON THE BOTTOM OF THE 6 IN. DEEP TRENCH. THE TRENCH SHALL BE BACKFILLED AND COMPACTED. 15.1.8. SEAMS BETWEEN SECTIONS OF SILT FENCE SHALL BE OVERLAPPED WITH THE END STAKES OF EACH SECTION WRAPPED TOGETHER BEFORE DRIVING INTO THE GROUND. 15.1.9. THE HEIGHT OF THE SILT FENCE SHALL BE A MINIMUM OF 16 IN. ABOVE THE ORIGINAL GROUND SURFACE AND SHALL BE A MAXIMUM OF 36" HIGH (HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE OF THE STRUCTURE). 15.1.10. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM OF A 6" OVERLAP, AND SECURELY SEALED. 15.1.11. POSTS SHALL BE SPACED AT A MAXIMUM OF 10 FEET APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND (MINIMUM OF 16"). WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE SUPPORT FENCE, POST SPACING SHALL NOT EXCEED 6'. 15.1.12. WHEN STANDARD STRENGTH FILTER FABRIC IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1" LONG, TIE WIRES OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2" AND SHALL NOT EXTEND MORE THAN 36" ABOVE THE ORIGINAL GROUND SURFACE. 15.1.13. THE STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE FENCE, AND 8" OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36" ABOVE THE ORIGINAL GROUND SURFACE. FILTER FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.		15.1.14. WHEN EXTRA STRENGTH FILTER FABRIC AND CLOSER POST SPACING ARE USED, THE WIRE MESH SUPPORT FENCE MAY BE ELIMINATED. IN SUCH A CASE, THE FILTER FABRIC IS STAPLED OR WIRED DIRECTLY TO THE POSTS WITH ALL OTHER PROVISIONS OF ITEM 15.1.10 APPLYING. 15.1.15. MAINTENANCE - SILT FENCES SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVERTOPS THE SILT FENCE, FLOWS UNDER OR AROUND THE ENDS, OR IN ANY OTHER WAY BECOMES A CONCENTRATED FLOW, ONE OF THE FOLLOWING SHALL BE PERFORMED AS APPROPRIATE: 15.1.15.1. THE LAYOUT OF THE SILT FENCE SHALL BE CHANGED. 15.1.15.2. ACCUMULATED SEDIMENT SHALL BE REMOVED. 15.1.15.3. OTHER PRACTICES SHALL BE INSTALLED. 15.1.16. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED. 15.2. CRITERIA FOR SILT FENCE MATERIALS 15.2.1. FENCE POSTS - THE LENGTH SHALL BE A MINIMUM OF 32 IN. LONG. WOOD POSTS WILL BE 2-BY-2IN. HARDWOOD OF SOUND QUALITY. THE MAXIMUM SPACING BETWEEN POSTS SHALL BE 10 FT. 15.2.2. SILT FENCE SHALL BE ODOT ITEM 712.09 TYPE C GEOTEXTILE FABRIC OR AS DESCRIBED BY THE FOLLOWING: 15.2.2.1. FABRIC PROPERTIES: 15.2.2.1.1. MINIMUM TENSILE STRENGTH 120 LBS 15.2.2.1.2. MAXIMUM ELONGATION AT 60 LBS150% 15.2.2.1.3. MINIMUM PUNCTURE STRENGTH 50 LBS 15.2.2.1.4. MINIMUM TEAR STRENGTH 40 LBS 15.2.2.1.5. APPARENT OPENING SIZE <0.84mm 15.2.2.1.6. MINIMUM PERMITTIVITY 1x10-2SEC-1 15.2.2.1.7. ULTRAVIOLET EXPOSURE STRENGTH RETENTION..... 70% 16. INLET PROTECTION 16.1. INLET PROTECTION SHALL CONSIST OF CATCH BASIN FILTERS INSTALLED OVER STORM INLET GRATES.				
B									
		DELAWARE COUNTY REGIONAL SEWER DISTRICT						CHECKED: AS DATE: JULY 2020	
		DESIGNED: WBS DRAWN: MRS						REVIEWED: RH	
C	STORM WATER DETAILS EROSION CONTROL NOTES		WOODS OF GLEN ERIN SANITARY SEWER IMPROVEMENTS				C		
		REVISION		DATE					


12.3.1. THESE PRACTICES ARE USED TO REDUCE THE RISK ASSOCIATED WITH HAZARDOUS MATERIALS.

12.3.1.1. PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE

12.3.1.2. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY CONTAIN IMPORTANT PRODUCT INFORMATION.12.4.1. THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ONSITE:

12.4.1.1. PETROLEUM PRODUCTS

12.4.1.1.1. ALL ONSITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.



DELAWARE COUNTY
REGIONAL SEWER DISTRICT

CHECKED: AS
DATE: JULY 2020

REVIEWED: RH

DESIGNED: WJB
DRAWN: MRB


STORM WATER DETAILS
EROSION CONTROL NOTES

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

G-4

P:\Projects\2018\2018-WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\G-5 Misc Details Rt.dwg Jul 01, 2020 - 1:04pm






EROSION & SEDIMENT CONTROL DETAILS

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

G-9

P:\Projects\2018\2040-WD-16563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet90 Submittal\Plan_Profiles_Rt.dwg Jul 01, 2020 4:12pm



DELAWARE COUNTY
REGIONAL SEWER DISTRICT


DESIGNED: WDB
CHECKED: JS
DATE: JULY 2020
DRAWN: MRB
REVIEWED: RH

PLAN & PROFILE
ERIN WOODS STA. 0+00
TO STA. 10+00

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS


REVISION	DATE

C-1



E

P:\Projects\2018\20H01\WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan_Profiles_R1.dwg Jul 01, 2020 - 3:38pm



CODED NOTES:

- ① TYPE A BACKFILL
- ② BRICK PAVER APRON TO BE REMOVED, PROTECTED & REINSTALLED TO PAYABLE LIMITS PER Sd.S-35

GENERAL NOTES:

1. REFERENCE DETAIL ① SHEET G-5 FOR BACKFILL REQUIREMENTS FOR SANITARY SEWER PARALLEL TO ROAD INSIDE THE ROW.

DELAWARE COUNTY
REGIONAL SEWER DISTRICT

DESIGNED: WOB

CHECKED: JS

DATE: JULY 2020

DRAWN: MBS

REVIEWED: MH


PLAN & PROFILE
ERIN WOODS STA. 18+00
TO STA. 27+00

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

C-3

P:\Projects\2018\20H01\WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan Profiles_R1.dwg Jul 01, 2020 - 3:45pm





CODDED NOTES:

- ① TYPE A BACKFILL
- ② RELOCATE TELEPHONE PEDESTAL FOR SANITARY SEWER INSTALLATION.
- ③ BRICK PAVER APRON TO BE REMOVED, PROTECTED & REINSTALLED TO PAYABLE LIMITS PER Sa.S-35

GENERAL NOTES:

1. REFERENCE DETAIL ① SHEET G-5 FOR BACKFILL REQUIREMENTS FOR SANITARY SEWER PARALLEL TO ROAD INSIDE THE ROW.



DELAWARE COUNTY
REGIONAL SEWER DISTRICT

PLAN & PROFILE
ERIN WOODS STA. 27+00
TO STA. 34+95.00

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

C-4

DATE:
JULY 2020


CHECKED:
JS

DESIGNED:
WOB

REVIEWED:
MH

DRAWN:
MBS

P:\Projects\2018\20H01WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan_Profiles_R1.dwg Jul 01, 2020 - 2:00pm



DELAWARE COUNTY
REGIONAL SEWER DISTRICT

DESIGNED: WOB
CHECKED: JS
DATE: JULY 2020

DRAWN: MBS
REVIEWED: MH


PLAN & PROFILE
SERENITY DR STA. 40+00
TO STA. 50+00

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

C-5


P:\Projects\2018\20H01WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan_Profiles_R1.dwg Jun 30, 2020 - 2:46pm



DELAWARE COUNTY REGIONAL SEWER DISTRICT	DESIGNED: WOB	CHECKED: JS	DATE: JULY 2020
	DRAWN: MBS	REVIEWED: MH	
	PLAN & PROFILE COMMON ACCESS DR STA. 50+00 TO STA. 57+45.00		
	WOODS OF GLEN ERIN SANITARY SEWER IMPROVEMENTS		

C-6

P:\Projects\2018\20H01WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan_Profiles_R1.dwg Jun 30, 2020 - 2:48pm



DELAWARE COUNTY
REGIONAL SEWER DISTRICT



DESIGNED: WOB
CHECKED: JS
DATE: JULY 2020
DRAWN: MBS
REVIEWED: MH

PLAN & PROFILE
SYLVIAN DR STA. 60+00 TO STA. 64+00 AND STA. 70+00 TO STA. 74+26
WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

REVISION	DATE

C-7

P:\Projects\2018\20401WD-18563 Woods of Glen Erin Delaware County\05 CADD Drawings\Sheet\90 Submittal\Plan_Profiles_R1.dwg Jul 01, 2020 - 1:59pm



- CODED NOTES:
- ① TYPE A BACKFILL
 - ② PRESSURE SERVICE LINE INSTALLED PER STD. DETAIL Sa.3-31
 - ③ CURB STOP AND BOX INSTALLED PER STD. DETAIL Sa.S-31
- GENERAL NOTES:
- REFERENCE DETAIL ① SHEET G-5 FOR BACKFILL REQUIREMENTS FOR SANITARY SEWER PARALLEL TO ROAD INSIDE THE ROW.



DELAWARE COUNTY
REGIONAL SEWER DISTRICT

DESIGNED: WDB	CHECKED: JS	DATE: JULY 2020
DRAWN: MRB	REVIEWED: RHT	

PLAN & PROFILE
SERENITY DR STA 80+00
TO STA. 82+74.00

WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS


REVISION	DATE

C-8

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT OF \$50 FOR EACH MINUTE THE ABOVE DESCRIBED LANE CLOSURE RESTRICTIONS ARE VIOLATED.

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE

P:\Projects\2019\20190101WD-18563 Woods of Glen Erin Delaware County\05 CADD - Drawings\Sheet90 Submittal\WOT plans.dwg Jul 01, 2020 - 7:46am



ODOT ITEM 614. PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS):
THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN, AND REMOVE, WHEN NO LONGER NEEDED, A CHANGEABLE MESSAGE SIGN TO NOTIFY THE PUBLIC OF TRAFFIC MODIFICATIONS AT LEAST ONE (1) WEEK PRIOR TO BEGINNING CONSTRUCTION. THE SIGN SHALL BE OF A TYPE SHOWN ON THE APPROVED LIST OF PCMS UNITS AVAILABLE ON ODOT'S OFFICE OF MATERIAL MANAGEMENT WEBSITE. THE LIST CONTAINS CLASS A AND CLASS B UNITS WITH MINIMUM LEGIBILITY DISTANCES OF 800 FEET AND 650 FEET, RESPECTIVELY.

EACH SIGN SHALL BE TRAILER-MOUNTED AND EQUIPPED WITH A FUNCTIONAL DIMMING MECHANISM, TO DIM THE SIGN DURING DARKNESS, AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. THE PCMS SHALL BE DELINEATED IN ACCORDANCE WITH ODOT CMS ITEM 614.03.

PCMS LOCATIONS SHALL BE DETERMINED BY THE SANITARY ENGINEER. PLACEMENT, OPERATION, MAINTENANCE, AND ALL ACTIVATION OF THE SIGNS CONTRACTOR SHALL BE AS DIRECTED BY THE SANITARY ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE SANITARY ENGINEER, RELOCATE THE PCMS TO IMPROVE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS SHALL BE TURNED OFF. ADDITIONALLY, WHEN NOT IN USE FOR EXTENDED PERIODS OF TIME, THE PCMS SHALL BE TURNED AWAY FROM ALL TRAFFIC.

THE SANITARY ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE DCRSD PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT, AND TO REVISE SIGN MESSAGES, IF NECESSARY.


ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE SANITARY ENGINEER. A LIST OF REQUIRED PRE-PROGRAMMED MESSAGES WILL BE GIVEN TO THE CONTRACTOR AT THE PROJECT PRE-CONSTRUCTION CONFERENCE. THE SIGN SHALL HAVE THE CAPABILITY TO STORE UP TO 99 MESSAGES. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS SHALL NOT BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. THREE-LINE PRESENTATION FORMATS WITH UP TO SIX (6) MESSAGE PHASES SHALL BE SUPPORTED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ TWICE. THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DEACTIVATED, OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.

THE PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF ODOT CMS ITEM 614. THE CONTRACTOR SHALL, PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS, WITH AN AUTHORIZED SERVICE AGENT FOR THE PCMS, TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT SIGN BEING OUT OF SERVICE FOR MORE THAN 12 HOURS, INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL TRAFFIC.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24-HOURS PER DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES WHEN THE PLAN REQUIRES THEIR USE.

PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE, AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.

OPEN-CUT TRENCHES:
OPEN-CUT TRENCH EXCAVATIONS SHALL BE BACKFILLED TO A DEPTH OF NO GREATER THAN THREE (3) INCHES BELOW THE EXISTING PAVEMENT PRIOR TO OPENING THE ROAD TO TRAFFIC. THE OPENING MUST BE PLATED AND THE PLATES SHALL BE RECESSED TO FIT NEATLY IN THE PAVEMENT OPENING TO PROVIDE A SUITABLE PASSAGE OF TRAFFIC AND SNOW REMOVAL EQUIPMENT. NO MORE THAN 200 LINEAR FEET OF PLATES SHALL BE PERMITTED IN PLACE AT ANY ONE TIME. PLATES IN USE ON THE ROADWAY SHALL BE A MINIMUM OF 1-INCH THICK AND BE IN A SMOOTH CONDITION, FREE OF BOWS OR ROUGH EDGES. THE PLATE IS TO EXTEND AT LEAST TWELVE (12) INCHES BEYOND THE TRENCH CUT. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THE TRENCH IS ADEQUATELY COVERED AND SAFE PASSAGE IS PROVIDED. PAYMENT FOR COVER PLATES SHALL BE INCLUDED IN THE LUMP SUM BID FOR DCRSD ITEM 315, TRAFFIC CONTROL.



- LEGEND:
- WORK ZONE
 - BARRELS
 - GRABBER CONES
 - MOT TEMPORARY SIGN
 - DIRECTION OF TRAVEL

DELAWARE COUNTY
REGIONAL SEWER DISTRICT

MAINTENANCE
OF TRAFFIC
NOTES & DETAILS


WOODS OF GLEN ERIN
SANITARY SEWER IMPROVEMENTS

DESIGNED: WDB	CHECKED: JS	DATE: JULY 2020
DRAWN: MRB	REVIEWED: RH	

REVISION	DATE

MT-2

P:\Projects\2018\20180101WD-18563 Woods of Glen Erin Delaware County\05 CADD-Drawings\Sheet90 Submittal\WOT plans.dwg Jul 01, 2020 - 7:47am



		A	
		B	
DELAWARE COUNTY REGIONAL SEWER DISTRICT		DESIGNED: WDB	CHECKED: JS DATE: JULY 2020
MAINTENANCE OF TRAFFIC DETAILS		DRAWN: MRB	REVIEWED: KH
WOODS OF GLEN ERIN SANITARY SEWER IMPROVEMENTS		C	
REVISION		DATE	
MT-3		D	
		E	